

1.6.3	G-EMBO aircraft information	20
1.6.3.1	Embraer 145 general description	21
1.6.3.2	Embraer 145 control system description.....	21
1.6.3.3	Embraer 145 brake system description	22
1.6.3.4	Embraer 145 performance.....	22
1.7	Meteorological information	22
1.7.1	Meteorological information relating to 29 December 2006	22
1.7.2	Meteorological information relating to 3 January 2007	23
1.7.3	Reported runway conditions for 29 December 2006 and 3 January 2007	24
1.8	Aids to navigation	24
1.9	Communications	24
1.9.1	Runway state reporting means and methods.....	24
1.9.2	Braking Action.....	26
1.9.3	UK AIP.....	27
1.9.4	‘ <i>Slippery when wet</i> ’	28
1.9.5	Notice to Aerodrome Licence Holders (NOTAL) 9/2006	28
1.9.6	Operational advice and information to flight crews.....	29
1.9.7	RFFS Communication	30
1.10	Aerodrome information	31
1.10.1	General	31
1.10.2	Runway resurfacing	31
1.10.2.1	Requirements for runway surfaces.....	31
1.10.2.2	Runway resurfacing work at BIA	32
1.10.2.3	Runway rectification work following incidents on 29 December 2006 and 3 January 2007	35
1.10.2.5	Independent runway surface inspection on 7 January 2007	37
1.11	Flight Recorders.....	37
1.11.1	Longitudinal Effects on G-XLAC	37
1.11.1.1	Deceleration vs. Runway Position	38
1.11.1.2	Deceleration Components.....	38
1.11.1.3	Braking Coefficient.....	41
1.11.2	Lateral Effects.....	43
1.11.2.1	G-BWDA	43
1.11.2.2	G-EMBO	44

1.12	Aircraft examinations	45
1.12.1	G-BWDA examination	45
1.12.2	G-EMBO examination.....	46
1.12.3	G-XLAC examination.....	46
1.13	Medical and pathological information	46
1.14	Fire	46
1.15	Survival aspects.....	46
1.16	Tests and research	46
1.17	Organisational and management information	46
1.17.1	ICAO and CAA action.....	47
1.18	Additional information.....	48
1.18.1	Friction Measuring Equipment	50
1.18.1.1	Douglas Mu-meter Mk6 CFME	50
1.18.2	Friction Measurement Data from BIA.....	51
1.18.3	Previous runway resurfacing works at Luton Airport.....	56
1.18.4	Previous runway resurfacing works at Belfast City Airport	57
1.18.5	Risk assessment carried out by BIA prior to runway resurfacing works.....	57
1.18.6	Hydroplaning	58
1.18.6.1	Estimated dynamic hydroplaning speeds for the incident aircraft	59
1.18.7	National Transportation Safety Board (NTSB) (USA) N471WN Chicago Midway International Airport investigation....	60
1.18.8	Previous incidents and AAIB Safety Recommendations.....	61
2	Analysis.....	62
2.1	Runway resurfacing	62
2.1.1	Planning of resurfacing works	62
2.2	Hydroplaning	64
2.3	Operation of the aircraft.....	65
2.3.1	G-XLAC	65
2.3.2	G-BWDA	66
2.3.2.1	Aircraft loading.....	66
2.3.2.2	Crosswind component.....	66
2.3.2.3	Runway condition	66
2.3.2.4	Effects of aileron handling and reverse thrust	67
2.3.2.5	NOTAMs.....	67
2.3.3	G-EMBO.....	67

2.4	Runway state reporting	68
2.5	FODCOMs as a means of promulgating operational safety information	69
2.6	CFME and wet runways.....	70
2.7	ATC	71
2.8	Braking coefficient.....	72
2.9	Communications	73
2.9.1	Safety action	73
3	Conclusions	74
3.1	Findings.....	74
3.1.1	The aircraft.....	74
3.1.2	The runway	74
3.1.3	Flight operations	75
3.1.4	Air traffic control	76
3.2	Causal Factors.....	77
3.3	Contributory Factors	77
4	Safety Recommendations.....	78

Appendices

Appendix A	BIA Runway Condition at 29 December 2006
Appendix B	Additional Mu-meter Friction Measurements
Appendix C	Additional Figures from FDR Data
Appendix D	Diagrams of G-BWDA and G-EMBO Runway Excursions
Appendix E	Flight crew details
Appendix F	The ‘Snow and Ice Table’